

Nota de Serviço Tabela

NOTA DE SERVIÇO DE TERRAPLANAGEM ROD MR 466 - 0+0.000 164+18.259

Lado Esquerdo				Eixo				Lado Direito			
OFFSET				P2				Estaca			
								Cota Projeto			
								Cota Terreno			
								Cota Vermelha			
Afast. (m)	Cota (m)	Incl. (%)	Afast. (m)	Cota (m)	Incl. (%)			Afast. (m)	Cota (m)	Incl. (%)	Afast. (m)
-6.527	7.803	-66.67	-5.850	8.254	-2.50	126+0.000	8.400	8.163	0.237	5.850	8.254
-7.102	7.419	-66.67	-5.850	8.254	-2.50	127+0.000	8.400	8.135	0.265	5.850	8.254
-7.066	7.443	-66.67	-5.850	8.254	-2.50	128+0.000	8.400	8.049	0.331	5.850	8.254
-6.923	7.539	-66.67	-5.850	8.254	-2.50	129+0.000	8.400	8.000	0.400	5.850	8.254
-6.960	7.514	-66.67	-5.850	8.254	-2.50	130+0.000	8.400	7.998	0.402	5.850	8.254
-6.915	7.543	-66.67	-5.850	8.254	-2.50	131+0.000	8.400	7.992	0.408	5.850	8.254
-7.457	7.183	-66.67	-5.850	8.254	-2.50	132+0.000	8.400	7.971	0.429	5.850	8.254
-7.127	7.402	-66.67	-5.850	8.254	-2.50	133+0.000	8.400	7.973	0.427	5.850	8.254
-7.042	7.459	-66.67	-5.850	8.254	-2.50	134+0.000	8.400	7.976	0.424	5.850	8.254
-6.858	7.582	-66.67	-5.850	8.254	-2.50	135+0.000	8.400	7.987	0.413	5.850	8.254
-7.070	7.441	-66.67	-5.850	8.254	-2.50	136+0.000	8.400	7.977	0.423	5.850	8.254
-6.898	7.555	-66.67	-5.850	8.254	-2.50	137+0.000	8.400	7.958	0.442	5.850	8.254
-6.858	7.582	-66.67	-5.850	8.254	-2.50	138+0.000	8.400	7.952	0.448	5.850	8.254
-6.842	7.592	-66.67	-5.850	8.254	-2.50	139+0.000	8.400	7.944	0.456	5.850	8.254
-6.618	7.742	-66.67	-5.850	8.254	-2.50	140+0.000	8.400	7.897	0.503	5.850	8.254
-6.564	7.777	-66.67	-5.850	8.254	-2.50	141+0.000	8.400	7.942	0.458	5.850	8.254
-6.250	7.987	-66.67	-5.850	8.254	-2.50	142+0.000	8.400	8.005	0.395	5.850	8.254
-6.758	7.648	-66.67	-5.850	8.254	-2.50	143+0.000	8.400	7.942	0.458	5.850	8.254
-6.424	7.871	-66.67	-5.850	8.254	-2.50	144+0.000	8.400	7.985	0.415	5.850	8.254
-6.141	8.060	-66.67	-5.850	8.254	-2.50	145+0.000	8.400	7.935	0.465	5.850	8.254
-6.482	7.832	-66.67	-5.850	8.254	-2.50	146+0.000	8.400	7.906	0.494	5.850	8.254
-6.680	7.700	-66.67	-5.850	8.254	-2.50	147+0.000	8.400	7.876	0.524	5.850	8.254
-6.780	7.634	-66.67	-5.850	8.254	-2.50	148+0.000	8.400	7.911	0.489	5.850	8.254
-6.311	7.946	-66.67	-5.850	8.254	-2.50	149+0.000	8.400	7.958	0.442	5.850	8.254
-6.838	7.595	-66.67	-5.850	8.254	-2.50	150+0.000	8.400	7.972	0.428	5.850	8.254
-6.842	7.592	-66.67	-5.850	8.254	-2.50	151+0.000	8.400	7.995	0.405	5.850	8.254
-6.745	7.657	-66.67	-5.850	8.254	-2.50	152+0.000	8.400	8.034	0.366	5.850	8.254
-6.626	7.737	-66.67	-5.850	8.254	-2.50	153+0.000	8.400	8.073	0.327	5.850	8.254
-6.436	7.863	-66.67	-5.850	8.254	-2.50	154+0.000	8.400	8.111	0.289	5.850	8.254
-6.407	7.883	-66.67	-5.850	8.254	-2.50	155+0.000	8.400	8.173	0.227	5.850	8.254
-6.660	7.714	-66.67	-5.850	8.254	-2.50	156+0.000	8.400	8.186	0.214	5.850	8.254
-6.441	7.860	-66.67	-5.850	8.254	-2.50	157+0.000	8.400	8.221	0.179	5.850	8.254
-6.226	8.003	-66.67	-5.850	8.254	-2.50	158+0.000	8.400	8.319	0.081	5.850	8.254

LITORAL SUL

PROJETOS DE ENGENHARIA

PREFEITURA MUNICIPAL DE MARACAJÁ

PROJETO DE PAVIMENTAÇÃO ASFALTICA DA RODOVIA MR 466

PROJETO GEOMÉTRICO

LEVANTAMENTO: ALAERCIO

ESCALA: SEM ESCALA

DATA: AGOSTO/2019

VERSÃO: 1/2

FOLHA: 3843