

			PLANILHA DE CÁLCULO DE QUANTITATIVOS DE TERRAPLENAGEM						
PREFEITURA MUNICIPAL DE MARACAJÁ				BAIRRO: CEDRO		MUNICÍPIO: MARACAJÁ		ESTADO: SANTA CATARINA	
				DATA: 18/03/24					
ESTACA			SEMI DISTÂNCIA	ÁREA DE CORTE	SOMA DAS ÁREAS	VOLUME DE CORTE	ÁREA DE ATERRO	SOMA DAS ÁREAS	VOLUME DE ATERRO
0	+	0,000		0,915			0,275		
1	+	0,000	10,000	1,577	2,492	24,920	0,191	0,466	4,660
2	+	0,000	10,000	1,055	2,632	26,320	0,147	0,338	3,380
3	+	0,000	10,000	0,420	1,475	14,750	0,258	0,405	4,050
4	+	0,000	10,000	0,371	0,791	7,910	0,342	0,600	6,000
5	+	0,000	10,000	0,380	0,751	7,510	0,420	0,762	7,620
6	+	0,000	10,000	0,323	0,703	7,030	0,367	0,787	7,870
7	+	0,000	10,000	0,237	0,560	5,600	0,517	0,884	8,840
7	+	17,417	8,709	0,185	0,422	3,670	0,621	1,138	9,910
8	+	0,000	1,292	0,185	0,370	0,470	0,629	1,250	1,610
9	+	0,000	10,000	0,217	0,402	4,020	0,637	1,266	12,660
10	+	0,000	10,000	0,515	0,732	7,320	0,385	1,022	10,220
10	+	9,816	4,908	0,882	1,397	6,850	0,273	0,658	3,220
11	+	0,000	5,092	1,271	2,153	10,960	0,173	0,446	2,270
11	+	7,280	3,640	1,240	2,511	9,140	0,186	0,359	1,300
11	+	17,418	5,069	1,593	2,833	14,360	0,122	0,308	1,560
12	+	0,000	1,291	1,693	3,286	4,240	0,106	0,228	0,290
13	+	0,000	10,000	2,014	3,707	37,070	0,053	0,159	1,590
13	+	19,489	9,744	2,171	4,185	40,780	0,007	0,060	0,580
14	+	0,000	0,256	2,135	4,306	1,100	0,008	0,015	0,000
15	+	0,000	10,000	1,131	3,266	32,660	0,124	0,132	1,320
16	+	0,000	10,000	0,872	2,003	20,030	0,263	0,387	3,870
17	+	0,000	10,000	0,641	1,513	15,130	0,801	1,064	10,640
17	+	19,489	9,744	0,446	1,087	10,590	0,915	1,716	16,720
18	+	0,000	0,256	0,446	0,892	0,220	0,917	1,832	0,460
19	+	0,000	10,000	0,556	1,002	10,020	0,434	1,351	13,510
20	+	0,000	10,000	1,122	1,678	16,780	0,677	1,111	11,110
20	+	6,787	3,393	1,293	2,415	8,190	0,772	1,449	4,910
20	+	7,827	0,520	1,303	2,596	1,340	0,779	1,551	0,800
21	+	0,000	6,087	0,970	2,273	13,830	0,649	1,428	8,690
21	+	1,592	0,796	0,953	1,923	1,530	0,619	1,268	1,000
22	+	0,000	9,204	1,328	2,281	20,990	0,041	0,660	6,070
22	+	16,806	8,403	1,644	2,972	24,970	0,108	0,149	1,250
23	+	0,000	1,597	1,862	3,506	5,590	0,132	0,240	0,380
23	+	7,827	3,914	2,408	4,270	16,710	0,311	0,443	1,730
23	+	19,117	5,645	2,383	4,791	27,040	0,255	0,566	3,190
24	+	0,000	0,441	2,394	4,777	2,100	0,251	0,506	0,220
25	+	0,000	10,000	2,348	4,742	47,420	0,112	0,363	3,630
26	+	0,000	10,000	0,624	2,972	29,720	0,731	0,843	8,430
26	+	9,117	4,558	0,345	0,969	4,410	1,533	2,264	10,320
27	+	0,000	5,442	0,474	0,819	4,450	2,046	3,579	19,470
27	+	14,253	7,127	0,871	1,345	9,580	1,167	3,213	22,890
28	+	0,000	2,873	1,078	1,949	5,600	0,951	2,118	6,080
29	+	0,000	10,000	1,481	2,559	25,590	0,611	1,562	15,620
30	+	0,000	10,000	0,974	2,455	24,550	0,620	1,231	12,310
30	+	9,117	4,558	0,670	1,644	7,490	0,615	1,235	5,620
31	+	0,000	5,442	0,415	1,085	5,900	0,655	1,270	6,910
32	+	0,000	10,000	0,752	1,167	11,670	0,386	1,041	10,410
32	+	5,407	2,704	0,919	1,671	4,510	0,334	0,720	1,940
32	+	18,819	6,706	0,851	1,770	11,860	0,323	0,657	4,400
33	+	0,000	0,591	0,861	1,712	1,010	0,311	0,634	0,370
34	+	0,000	10,000	1,102	1,963	19,630	0,197	0,508	5,080
34	+	5,407	2,704	1,016	2,118	5,720	0,250	0,447	1,200
35	+	0,000	7,296	1,132	2,148	15,670	0,200	0,450	3,280
36	+	0,000	10,000	1,291	2,423	24,230	0,442	0,642	6,420
36	+	5,803	2,902	1,432	2,723	7,900	0,522	0,964	2,790
37	+	0,000	7,099	1,009	2,441	17,320	0,714	1,236	8,770
37	+	15,636	7,818	0,470	1,479	11,560	1,186	1,900	14,850
38	+	0,000	2,182	0,343	0,813	1,770	1,620	2,806	6,120
39	+	0,000	10,000	0,239	0,582	5,820	4,864	6,484	64,840
39	+	2,524	1,262	0,254	0,493	0,620	4,894	9,758	12,310
39	+	15,038	6,257	0,343	0,597	3,730	5,126	10,020	62,690
39	+	15,636	0,299	0,352	0,695	0,200	5,126	10,252	3,060
40	+	0,000	2,182	0,423	0,775	1,690	5,059	10,185	22,220
						771,360			
						VOLUME TOTAL DE ESCAVAÇÃO:		771,360	
						VOLUME TOTAL DE ATERRO:		515,530	
						BOTA FORA:		255,830	